


TEST REPORT

No. 01-2013

Applicant: RZ-Products GmbH
Industriestr. 41
57518 Betzdorf

Content of order: Proof of tightness against water heights of 500 mm for at least 72 hours and a leakage rate of less than 1 liter.

Test specimen: Modular IT Security Room incl. door and cable duct


Type: 

Date of test: 15.01.2013 – 18.01.2013

Test result: **The tested IT Security Room, type „Granite-Room.cert“ offers protection against water columns of 500 mm for a period of at least 72 hours and a leakage rate of less than 1 liter from water¹ penetration.**

Test report: 3 pages text and 5 pages appendix

Issued by: **Engineering office for structural planning and design**



DIPL.ING. H.-J. BIERBRAUER

TRAGWERKSPLANUNG ▪ ENTWURFSPLANUNG
CAD-BAUKONSTRUKTION ▪ SIGE-KOORDINATOR

Bahnhofstraße 7 57648 Unnau

Telefon: +49 (0) 26 61 - 98 46 88 2 Fax: +49 (0) 26 61 93 9576

Mobil: +49 (0) 171 - 34 43 20 3

E-mail: HBierbrauer@gmx.de

Unnau, 19.01.2013



Dipl. Ing. H.-J. Bierbrauer

¹ The min. required height of the door step is 400 mm, otherwise additional sealings of the security room door are required.